



NORWOOD-WESTWOOD
US ROUTE 1 (BOSTON-PROVIDENCE HWY)

DATE	ISS. NO.	SHEET	TOTAL SHEETS
NA		1	1

PROJECT FILE NO. XXXXXX

CONCEPTUAL IMPROVEMENT PLAN
OPTION 3
(RTE 1 DOUBLE LT & EXTENDED
AUXILIARY THROUGH LANES
W/EVERETT ST MEDIAN)

RTE 1 NB CONST BL DATA

STARTING STATION	CURVE DATA	LINE DATA	ENDING STATION
82+00.00		N16°34'49"E 1104.10'	93+04.10
93+04.10	R=11000.00 L=746.52 Δ=7°53'18" T=373.40'		100+50.62
100+50.62		N20°28'07"E 455.09'	105+05.71
105+05.71		N19°19'22"E 1059.94'	115+65.65
115+65.65	R=604.00 L=1001.30 Δ=8°57'31" T=501.67'		125+66.95

RTE 1 SB CONST BL DATA

STARTING STATION	CURVE DATA	LINE DATA	ENDING STATION
393+04.10		N16°34'49"E 661.26'	399+85.36
399+85.36	R=8000.00 L=870.75 Δ=6°14'11" T=425.81'		408+56.11
408+56.11	R=20803.39 L=471.27 Δ=1°17'53" T=233.65'		413+27.39
413+27.39	R=6398.00 L=240.25 Δ=2°06'05" T=120.14'		415+67.63

UNIVERSITY AVE-EVERETT ST CONST BL DATA

STARTING STATION	CURVE DATA	LINE DATA	ENDING STATION
415+77.76	R=1003.00 L=610.53 Δ=35°12'09" T=318.36'		421+04.29
421+04.29		N62°17'26"W 347.52'	425+41.83
425+41.83	R=991.00 L=966.43 Δ=32°41'27" T=290.64'		431+07.25
431+07.25		N60°24'07"E 3.00'	431+07.25
431+07.25		N20°33'59"W 323.00'	434+30.25
434+30.25	R=1016.00 L=488.17 Δ=28°02'37" T=254.29'		439+28.42
439+28.42		N57°41'36"W 30.02'	439+58.45
439+58.45	R=1030.00 L=359.39 Δ=19°59'31" T=181.54'		443+17.94